Outlook

$250 extension fee
Paid 10/20/2026

CUP Extension

From Seven Spuds <[redacted]>
Date Sun 10/25/2026 10:11 AM
To Lori Hunter <lhunter@valleycountyid.gov>

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

RE: Olsen Solar Panel CUP.

To whom it may concern,

I am requesting an extension of the CUP for the solar panel array at 16 East Mountain Road for an additional year. While the project was nearing completion, work was halted to first meet the permitting requirements of the building department. I will also have to wait until next spring to replace the schedule 40 PVC conduit placed already, as I was unaware schedule 80 is required for all above ground conduit. I will also need extra time to complete the other action items DOPL has identified in the rough in inspection.

Thank you ,

Shayne Olsen

Olsen Solar Off Grid ground mounted system



Location of Panels

Scope of Project

1- Provide electric power to Storage building on property where no utility power is available. The system will be constructed to provide 3.2 KW of solar power with 10 KW of battery storage. Primary purpose is to provide on site power and minimize/eliminate the need for portable generator use.

System Components

1. Hyperion 405 W bifacial solar panels (8 Total).
2. One EG4 brightmount solar mounting system (4 panels mounted- angled).
3. 4 - vertically mounted panels - Fencing standard posts and galvanized fence pipe..
4. Both 4 panel strings are equipped with Fuse protection/Surge protection on panel mounting..
5. All wiring enclosed in PVC electrical Conduit. Schedule 80 above and schedule 40 below ground.
6. All PV wire is 10 AWG standard red/black stranded copper PV wire. (Including grounding/bonding wire.)
7. 1 Sungold Power model SPH5048P inverter / charger.
8. 2 Sungold Power model SG48100P solar rack batteries.